

Well 27 Blending Project				
Estimated Construction Cost \$300,000				
May 5, 2017				
CONCO WEST INC. - MANTECA, CA				
ITEM NO.	ITEM DESCRIPTION	BID QTY	UNIT	EXTENDED PRICE
1	Mobilization and Demobilization	1	LS	\$ 20,000.00
2	Pothole Items per Plan	1	LS	\$ 9,600.00
3	Construction Signs	1	LS	\$ 1,000.00
4	Traffic Control	1	LS	\$ 15,000.00
5	Saw-Cut AC	590	LF	\$ 2,360.00
6	Trench Patch (5" AC/6" AB) on W. Lathrop Road	885	SF	\$ 10,600.00
7	Connect to Existing Water Mains	2	EA	\$ 4,200.00
8	Provide and Install 10-in Gate Valves	2	EA	\$ 6,000.00
9	Install only of 10-in CLA-VAL (City will supply valve)	1	EA	\$ 600.00
10	Install only of 10-in Mag Meter (City will supply meter)	1	EA	\$ 600.00
11	10-in PVC C900 DR 18 (235 PSI) includes all fittings, thrust blocks, pipe restraints, shoring, and trench back fill, and G-5 valve box with lid	520	LF	\$ 59,800.00
12	10-in DIP AWWA Class 50 Piping includes all fittings, pipe restraints, and pipe supports	25	LF	\$ 18,750.00
13	Pressure test and disinfect water mains per AWWA most recent Standard	1	LS	\$ 3,000.00
14	Install and provide 5, 1.25-in Schedule 40 PVC with rigid steel risers	280	LF	\$ 8,680.00
15	2-inch Schedule 40 PVC conduit for future Fiber Optics	170	LF	\$ 4,250.00
16	Future Fiber Optics pull boxes P-48	2	EA	\$ 3,200.00
17	3/4" PVC Water Line to Well 27 Building	40	LF	\$ 4,800.00
18	Removable Bollards	8	LS	\$ 6,000.00
19	Building Permits	1	LS	\$ 2,600.00
20	Provide interim water line connections	2	LS	\$ 1,600.00
21	Caltrans Pavement Marker Detail 39	50	LF	\$ 150.00
22	Caltrans Pavement Marker Detail 32	350	LF	\$ 2,100.00
23	2-Way Left Turn Arrow - (Arrow Type III)	1	EA	\$ 450.00
24	Water Pollution Control	1	LS	\$ 900.00
BID TOTAL:				\$ 186,240.00